

317 SEWER/WATER PCC FORMWORK CONSTRUCTION

317.01 DESCRIPTION

Work includes furnishing all labor, materials, equipment and incidentals required to provide formwork for all PCC structures as shown on Drawings and as specified herein.

317.02 SUBMITTALS

Working drawings shall be prepared in accordance with 703.14(A) and (B) and submitted in accordance with 105.02.

317.03 MATERIALS.

PCC Formwork - 703.14

Sewer/Water PCC Accessories - 319

317.04 CONSTRUCTION REQUIREMENTS

Formwork and falsework shall be placed in accordance with 703.14 and 703.16 and removed in accordance with 703.17.

317.05 MEASURE AND PAYMENT

PCC formwork will not be measured separately for payment; the cost thereof shall be included in the lump sum or unit price for PCC items of which it is a part.