

318 REINFORCING STEEL - SEWER/WATER WORK

318.01 DESCRIPTION

Work includes furnishing all labor, materials, equipment and incidentals required and installing all reinforcing steel required for the reinforcement of PCC, as shown on the Drawings and as specified herein.

318.02 SUBMITTALS

Shop drawings shall be submitted in accordance with 704.03.

318.03 MATERIALS

Reinforcing Steel - 812.02, Grade 60

318.04 CONSTRUCTION REQUIREMENTS

Fabrication, protection and placement of reinforcing steel shall be performed in accordance with requirements of 704.04 through 704.08.

318.05 MEASURE AND PAYMENT

PCC reinforcement will not be measured separately for payment; the cost thereof shall be included in the lump sum or unit price for PCC items of which it is a part.