

411 TEMPORARY ASPHALT CONCRETE

411.01 DESCRIPTION

Work shall consist of furnishing, hauling and placing hot asphaltic concrete in areas designated by the Engineer for temporary connections to existing roadways, sidewalks and detours as shown on the plans or as directed by the Engineer, as may be necessary to maintain pedestrian and vehicular traffic and to protect protruding street structures, expansion dams, etc. Work shall include the removal and disposal of Temporary Asphalt Concrete when no longer required.

411.02 MATERIALS

Temporary Asphalt Concrete shall meet the requirements of 403 for Hot Asphaltic Concrete, Class C.

411.03 ALTERNATE

In case of emergency, when the specified material is not readily obtainable, a suitable hot asphaltic concrete material may be substituted as an equivalent alternate, subject to prior approval of the Engineer.

In case of extreme emergency, when the specified material is not readily obtainable, and a suitable hot asphaltic concrete material is not available, a cold asphalt mix may be substituted as an equivalent alternate, subject to prior approval of the Engineer.

411.04 MEASURE AND PAYMENT

Measure and Payment for Temporary Asphalt Concrete shall be made in conformance with 403.04. Payment will include removal and disposal of materials no longer needed.