

## **416 ASPHALT BIKE PATH**

### **416.01 DESCRIPTION**

This work shall consist of constructing a hot asphaltic concrete bike path on a prepared grade to the line, grade and dimensions specified in the contract documents.

### **416.02 MATERIALS**

Hot Asphaltic Concrete Surface - 818 for the Type specified.

### **416.03 CONSTRUCTION REQUIREMENTS**

The pertinent provisions of 401 apply except that a 3 to 5 ton roller shall be used to obtain the required compaction. A 3 wheel roller will not be required. Hand work in certain areas may be approved when machine-laid asphalt would be impracticable.

### **416.04 MEASURE AND PAYMENT**

The unit of measure for Asphalt Bike Path will be the ton. The actual number of tons of hot asphaltic concrete used will be paid for at the contract unit price per ton, which payment will include furnishing all labor, equipment, materials and other incidentals necessary to complete the work as specified.